CAPSULE SUMMARY SHEET

Survey No.: CH-244 (PACS B9)		Construction Date:circa 1905		
Name: Page Property				
location: 4415 and 4415	R Middletown Road	Pomfret vicinity (Charles County	

Private/Private residence/Occupied/Deteriorated/Not accessible

Description:

The Page Property is a 2-story, 3-bay, side-gable I-house with a center gable. The property, which has been converted to a duplex, is located on the west side of Middletown Road in the Pomfret vicinity, Charles County. Constructed circa 1905, it is clad in aluminum siding and is supported by concrete piers. It has a metal roof with two central brick chimneys and most of the windows in the structure are 2/2 double-hung sash; two windows on the north elevation are 6/6 double-hung sash.

Significance:

The Page Property is an I-house, a common early twentieth century architectural style, which is undistinguished by any features or details. The installation of aluminum siding, coupled with the considerable deterioration of the property has compromised its architectural integrity. The Page Property was originally situated on approximately 81.34 hectare (201 acres) of "Oak Grove" acquired in 1904 through the division of the estate of Mary B. Page. A house was constructed on the land circa 1905. The parcel associated with the residence was reduced to 28.32 hectare (70 acres) in 1912 when the Page heirs conveyed the property to Washington C. Page. The lot was further reduced to 24.28 hectare (60 acres) when Washington Page sold the property in 1915. The current owner, Julian Carr, acquired the property in 1937, and has subsequently reduced the size of the parcel associated with the premises to 13.15 hectares (32.5 acres).

Survey No.: CH-244 (PACS B9)

DOE ___yes ___no

Maryland Historical Trust Maryland Inventory of Historic Properties Form U.S. 301 South Corridor Transportation Study

		* *		- 		劃
1. Name:	(indicate preferred	name)	_ =		_	
historic Page	Property					
and/or common	Julian Carr Property	5			9	
2. Locat	ion:					
street & number	4415 and 4415B Middlet	own Road			not for p	ublication
city, town Pomfi	ret	_x_ vicini	ty of	con	gressional	district
state Mary	land	county Cha	ırles			
3. Class	ification:					
Categorydistrict _x_building(s)structuresiteobject	Ownershippublic _x_privateboth Public Acquisitionin processbeing considered _x_not applicable	Status _x_occupiedunoccupie _work in p Accessibleyes: rest _yes: unre _x_no	rogress	govern indust: milita:	lture _ cial _ ion _ ainment ment _ rial _	museumpark x_private residence _religious _scientific _other:
4. Owner	of Property:	(give names	and maili	ng addresse	s of <u>all</u> o	wners)
name Julian Carr	?					
street & number	1474 Harvard Street, N.	w.			telep	hone no.:
city,town Washir	ngton			state and	d zip code	DC 20009
5. Locat	ion of Legal	Descript	ion			
Land Records Offi	ice of Charles County					liber 67
street & number	101 Catalpa Drive					folio 204
city,town	La Plata		7/1		8	tate MD
6. Repre	sentation in	Existing	Histo	rical	Surve	ys
title					-	
date			_federal	state	county	local
depository/survey	/ records					
city, town						state

7. Description

Survey No.: CH-244 (PACS R9)

Condition		Check one	Check one	
excellent good fair	<u>x</u> deteriorated ruins unexposed	unaltered _x_altered	<u>x</u> original site moved	date of move

Resource Count: 1

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Page Property is a 2-story, 3-bay, side-gable I-house with a central cross-gable. The property, which has been converted to a duplex, is located on the west side of Middletown Road in the Pomfret vicinity, Charles County. Constructed circa 1905, it is clad in aluminum siding and it is supported by concrete piers. It has a metal roof with two central brick chimneys and most of the windows in the structure are 2/2 double-hung sash; two windows on the north elevation are 6/6 double-hung sash.

The first story of the east, or front elevation has one 2/2 double-hung window in the first bay. There are wood doors with four lights in both the second and third bays. The second story has three 2/2 double-hung windows.

The south elevation has one 2/2 double-hung window on both the first and second stories.

The west, or rear elevation has three, 1-story shed-roof additions. The addition in the center of the elevation has a central brick chimney. The second story of the elevation has two 2/2 uble-hung windows.

The north elevation has one 6/6 double-hung window on both the first and second stories.

The Page Property is located on the west side of Middletown Road. Its setting remains rural, as it is bordered on the north, south and west by wooded land.

8. Significance

Survey No.: CH-244 (PACS B9)

1400-149 1500-159 1600-169 1700-179 1800-189	Areas of Significance—Check and justicearchaeology-prehistoricCommunity planningarcheology-historicconservationagricultureeconomicsarchitectureeducationartengineeringcommerceexploration/settlementcommunicationindustryinvention	landscape architecturereligionlaw
Specific d	lates circa 1905	Builder/Architect
check:	Applicable Criteria:ABC and/or Applicable Exceptions:ABC Level of Significance:national	DDEFGstatelocal

Prepare both a summary paragraph of significance and a general statement of history and support.

The Page Property was originally situated on approximately 81.34 hectare (201 acres) of "Oak Grove" acquired in 1904 through the division of the estate of Mary B. Page. A house was constructed on the land circa 1905. The parcel associated with the residence was reduced to 28.32 hectare (70 acres) in 1912 when the Page heirs conveyed the property to Washington C. Page. e lot was further reduced to 24.28 hectare (60 acres) when Washington Page sold the property in 1915. The current owner, Julian Carr, acquired the property in 1937, and has subsequently reduced the size of the parcel associated with the premises to 13.15 hectare (32.5 acres).

The Page Property is located in southern Maryland, in northern Charles County. The Native American inhabitants of southern Maryland from the Piscataway and Potobac nations were joined by European settlers beginning in 1634 with the establishment of St. Mary's City by Leonard Calvert. Successive waves of colonists took up tracts of land further inland from the Chesapeake Bay along the Patuxent and Potomac rivers and their tributaries. Charles County was formed in 1658 and Prince George's County was established in 1696. Settlement was confined to inland areas until road clearing began in the mid-eighteenth century as a result of the establishment of port towns and Maryland's rising population. Tobacco cultivation dominated the economic and social life of both Charles and Prince George's counties until the mid-nineteenth century when soil exhaustion necessitated agricultural diversification. The introduction of rail lines in 1873 linked Prince George's and Charles counties with the surrounding area, encouraging trade and settlement. While the suburbanization of Prince George's and Charles counties was ensured by the widespread availability of the automobile in the mid-twentieth century, these southern Maryland counties have also retained their rural and agricultural character.

A standard I-house, such as the Page Property, is one room deep and two stories tall with three to five openings on each story. From the front, an I-house is often indistinguishable from a Georgian house. The gable view, however, reveals the greater depth of the Georgian house. Chimneys are located on the interior of the gable ends, however, external chimneys are characteristic in the Chesapeake region. Usually, an I-house has a one-story porch running the length or nearly the length of the long side. On the interior, a central hall separates the two oms on the first floor; the second floor contains either two or four sleeping chambers. Due the narrowness of the main core, many I-houses have kitchen wings to the rear. Initially,

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

ESOURCE NAME: Page Property SURVEY NO.: CH-244 (PAGS B9)

ADDRESS: 4415 and 4415B Middletown Road, Pomfret vicinity, Charles County

8. Significance (Continued)

stone masonry construction was used but by the mid-nineteenth century, as pre-cut lumber became increasingly available, frame construction became the norm. During the Victorian period, pre-cut detailing or a two-tiered porch was commonly grafted onto the traditional I-house. The I-form was popular into the early twentieth century, with examples appearing in catalogs of mass-produced suburban houses (Gowans 1992, 55-6).

NATIONAL REGISTER EVALUATION:

The Page Property, a circa 1905 I-house, is not eligible for the National Register of Historic Places. The property is not eligible under Criterion A or B, as research indicates it has no association with historically significant persons or events. The residence is a common early twentieth century architectural style, which is undistinguished by any features or details. The installation of aluminum siding, coupled with the considerable deterioration of the property has compromised its architectural integrity, and therefore, it does not meet Criterion C. Finally, the property is not eligible under Criterion D, as it has no known potential to yield important information.

Eligibility Recommended	MARYLAND HISTORICAL TRUST Eligibility Not Recommended X
Comments:	
Reviewer, OPS: Suzanı	ne Pickens Date: 07/21/1997

Page 8.1 P.A.C. Spero & Company September 1996

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Page Property SURVEY NO.: CH-244 (PACS B9)

ADDRESS: 4415 and 4415B Middletown Road, Pomfret vicinity, Charles County

8. Significance (Continued)

stone masonry construction was used but by the mid-nineteenth century, as pre-cut lumber became increasingly available, frame construction became the norm. During the Victorian period, pre-cut detailing or a two-tiered porch was commonly grafted onto the traditional I-house. The I-form was popular into the early twentieth century, with examples appearing in catalogs of mass-produced suburban houses (Gowans 1992, 55-6).

NATIONAL REGISTER EVALUATION:

The Page Property, a circa 1905 I-house, is not eligible for the National Register of Historic Places. The property is not eligible under Criterion A or B, as research indicates it has no association with historically significant persons or events. The residence is a common early twentieth century architectural style, which is undistinguished by any features or details. The installation of aluminum siding, coupled with the considerable deterioration of the property has compromised its architectural integrity, and therefore, it does not meet Criterion C. Finally, the property is not eligible under Criterion D, as it has no known potential to yield important information.

Eligibility Recommended	MARYLAND HISTORICAL TRUST Eligibility Not Recommended
Reviewer, OPS:	Annoh I Date: 1914/99
Reviewer, NR Program:	Date:

9. Major Bibliographical References Survey No.: CH-244 (PACS_B9) See Continuation Sheet Geographical Data 10. Acreage of nominated property Quadrangle name La Plata, MD Quadrangle scale 1:24,000 Verbal boundary description and justification List all states and counties for properties overlapping state or county boundaries state code county code state code county code Form Prepared By 11.

name/title Caroline Hall

ganization P.A.C. Spero & Company

date September 1996

street & number 40 W. Chesapeake Avenue, Suite 412

telephone (410) 296-1635

city or town Baltimore state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposed only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

DHCP/DHCD

100 Community Place

Crownsville, MD 21032-2023

(410) 514-7600

CONTINUATION SHEET

MARYLAND HISTORICAL TRUST

STATE HISTORIC SITES INVENTORY FORM

RESOURCE NAME: Page Property SURVEY NO.: CH-244 (PACS 89)

ADDRESS: 4415 and 4415B Middletown Road, Pomfret vicinity, Charles County

9. Major Bibliographical References (Continued)

- Brown, Jack D., et al. <u>Charles County, Maryland, A History</u>. Charles County Bicentennial Committee, 1976.
- Charles County Retired Teachers Association. <u>A Legacy: One- and Two-Room Schools in Charles County</u>. La Plata: Dick Wildes Publishing Company, 1984.
- Gowans, Alan. Styles and Types of North American Architecture. New York: Harper Collins, 1992.
- Klapthor, Margaret Brown, and Paul Dennis Brown. <u>The History of Charles County, Maryland</u>. La Plata: Charles County Tercentenary, Inc., 1958.
- La Plata Courthouse Centennial. Supplement to the <u>Maryland Independent</u> and the <u>La Plata/Indian</u> <u>Head Ledger</u>. September 8, 1996.
- Martenet, Simon J. Martenet's Map of Maryland, Atlas Edition. Baltimore, 1866.
- Maryland Geological Survey. [1840] Map of Eastern Maryland with 1860 Additions. Copy on file at Maryland Historical Trust, Crownsville, MD.
- McDaniel, George W. <u>Hearth and Home, Preserving a People's Culture</u>. Philadelphia: Temple University Press, 1982.
- Rivoire, J. Richard. <u>Homeplaces, Traditional Domestic Architecture of Charles County, Maryland</u>. La Plata: Southern Maryland Studies Center, 1990.
- Wearmouth, John M. <u>Charles County Railroad</u>. An unpublished paper on deposit at the Prince George's County Historical Society. August 1984.
- Ibid. <u>La Plata, Maryland, 1888-1988, 100 Years, The Heart of Charles County</u>. La Plata: Town of La Plata, 1988.

Maryland Comprehensive Historic Preservation Plan Data Sheet

Page Property; CH-244 (PACS B9) 4415 and 4415B Middletown Road, Pomfret vicinity, Charles County

storic Context:

MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization:

Western Shore

Chronological/Developmental Period Theme (s):

Industrial/Urban Dominance A.D. 1870-1930

Prehistoric/Historic Period Theme(s):

Architecture

RESOURCE TYPE:

Category (see Section 3 of survey form):

Buildings; Private Ownership; Public Acquisition - Not applicable; Occupied; Not accessible; Private Residence

Historic Environment (urban, suburban, village, or rural):


Rural

Historic Function(s) and Use(s):

Residence

Known Design Source (write none if unknown):

None





1. CH = 244 2. PAGE PROPERTY, CHARLES CO, MO 3. CAROLINE HALL, 9/96 4. P.A.C. Speio & Comp. 40 W. Chesapeake Avenue, Suite 42 BALTMORE, MD 21204 5. 4415 and 4415B Middletown Road South and 6. 10f 5 Main hours & Northwest View



1. CH-244 2. PAGE PROFERTY, CHARLES CO, MD 3. CARDLINE HALL, 9/96 4. P. L.C. Speto & Co. 40 W. Chesapeato Avenue, Suite 412 BALTIMORE MO 212011 5, 4415 and 4415 B Middle town Royd North and Wast elevations of Main house 6.20f5 Southogs View



1. CH-244 2. Page Property, CHARLES CO, ME 3. Caroline Hall 4. P.A.C. Spend + Co, 40 W. Chesapeake Are #412. Balto, and 21204 5. 4415 and 44 BB Middletown Read 6.30f5 East elevation of house west view



1, CH-244 2. Page Property, THARLES CO. MD 3. Caroline Hall 9/96 4. P.A. C. Spero + Co. 40 W. Chesapeale Hve, # 412 Ba HO, 110 21204 5. 4413 and 4418B Middleton Board West 6. 4 of 5 elevation of house East view



2. POSE TISSETTY, SHARLES CO, MO 3. Carona Viali 9/96 A.P.A.C. Sjecto + Co. 40 W. Chesapleake the, #412, Balto, md 2104 5, 4415 and 4415B Middleton Boad South 6. 5 of 5 elevation of Main house North